					ST DEPARTMENT DIVISION O	OF NA					AMEN	FC DED REPC	ORT		
		APP	LICATION	FOR P	ERMIT TO DRILL	L				1. WELL NAME and		<b>R</b> -33-8-16			
2. TYPE (		RILL NEW WELL	REENT	ER P&A	WELL DEEPE	EN WELL	-0			3. FIELD OR WILDO		NT BUTTE			
4. TYPE (	OF WELL	Oil	Well	Coalbed	Methane Well: NO					5. UNIT or COMMUNITIZATION AGREEMENT NAME GMBU (GRRV)					
6. NAME	OF OPERATOR	<b>t</b>			TON COMPANY					7. OPERATOR PHONE					
8. ADDRI	SS OF OPERA									435 646-4825  9. OPERATOR E-MAIL mcrozier@newfield.com					
	RAL LEASE N		Rt 3 B0x 363		on, UT, 84052 <b>11. MINERAL OWNE</b>	RSHIP	•			12. SURFACE OWN		емпеіа.сс	·m		
		R STATE) UTU-77338 OWNER (if box :	12 = 'fee')		FEDERAL IND	DIAN (	) STATE (	) FEE(	<u> </u>	FEDERAL INI	DIAN \Bigg	STATI		FEE	
15. ADDI	RESS OF SURF	ACE OWNER (if b	ox 12 = 'fee	·')						16. SURFACE OWN	ER E-MA	IL (if bo)	12 = 'fe	ee')	
					18. INTEND TO COM	MING	I E PPODUCT	TON FROM	1	19. SLANT					
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')  WILTIPLE FORMATIONS YES (Submit Commingling Application) NO (III)  VERTICAL DIRECTIONAL (III) HORIZONTA								ITAL 🛑							
20. LOC	ATION OF WE	LL		FOO'	TAGES	Q1	rr-QTR	SECT	ION	TOWNSHIP	R	ANGE	МЕ	RIDIAN	
LOCATION	ON AT SURFAC	DE	7	82 FNL	769 FWL	N	IWNW	3		9.0 S	10	5.0 E		S	
Top of Uppermost Producing Zone 256 FNL 233 FWL NWNW 3							9.0 S		10	16.0 E		S			
At Total Depth 269 FSL 265 FEL							SESE	33		8.0 S	16	5.0 E		S	
21. COU		DUCHESNE		2	22. DISTANCE TO N		T LEASE LIN	E (Feet)		23. NUMBER OF AC		DRILLING 0	UNIT		
					25. DISTANCE TO N (Applied For Drilling	g or Co		AME POOI	L	26. PROPOSED DEF	PTH : 6597	TVD: 65	97		
27. ELEV	ATION - GROU	JND LEVEL		2	28. BOND NUMBER		J2			29. SOURCE OF DR			TE 400	TCARLE	
		5660				WYBO	000493			WATER RIGHTS AP	437		TF APPI	LICABLE	
Ch. i.e.	11-1-6'	G! G'		307.1.	Hole, Casing,				1			CI	X2 - 1 -1	NA / - ! - ! - !	
String Surf	Hole Size	Casing Size 8.625	0 - 300	Weig 24.			Max Mu			Class G		Sacks 138	Yield 1.17	Weight 15.8	
Prod	7.875	5.5	0 - 6597	15.			8.3		Prem	nium Lite High Stre	ngth	318	3.26	11.0	
										50/50 Poz		363	1.24	14.3	
					A	TTACH	IMENTS								
	VERIFY T	HE FOLLOWIN	G ARE ATT	ACHE	D IN ACCORDAN	CE W	ITH THE U	TAH OIL	AND (	GAS CONSERVATI	ON GE	NERAL F	RULES		
<b>✓</b> w	ELL PLAT OR	MAP PREPARED E	BY LICENSED	SURV	EYOR OR ENGINEER	R	Г сом	IPLETE DR	ILLING	PLAN					
AF	FIDAVIT OF S	TATUS OF SURFA	ACE OWNER	AGREE	MENT (IF FEE SURF	ACE)	FOR	4 5. IF OP	ERATO	R IS OTHER THAN T	HE LEAS	E OWNER	ł		
DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY TOPOGRAPHICAL MAP															
NAME M	andie Crozier				TITLE Regulatory	Tech			PHO	NE 435 646-4825					
SIGNAT	URE				<b>DATE</b> 04/27/2011				EMAI	L mcrozier@newfield.	com				
	MBER ASSIGN 013506940				APPROVAL				B	.00.64jll					
									Pe	ermit Manager					

# NEWFIELD PRODUCTION COMPANY GMBU U-33-8-16 AT SURFACE: NW/NW (LOT #4) SECTION 3, T9S, R16E DUCHESNE COUNTY, UTAH

#### TEN POINT DRILLING PROGRAM

#### 1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

#### 2. <u>ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:</u>

 Uinta
 0' – 1680'

 Green River
 1680'

 Wasatch
 6330'

 Proposed TD
 6597'

#### 3. <u>ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:</u>

Green River Formation (Oil) 1680' – 6330'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

Location & Sampled Interval Date Sampled Flow Rate Temperature

Hardness pH

Water Classification (State of Utah)

Dissolved Calcium (Ca) (mg/l)

Dissolved Iron (Fe) (ug/l)

Dissolved Magnesium (Mg) (mg/l)

Dissolved Bicarbonate (NaHCO<sub>3</sub>) (mg/l)

Dissolved Sulfate (SO<sub>4</sub>) (mg/l)

Dissolved Total Solids (TDS) (mg/l)

#### 4. PROPOSED CASING PROGRAM

a. Casing Design: GMBU U-33-8-16

Size	Interval		Weight	Grade	Coupling	Design Factors			
Size	Тор	Bottom	vveigni	Grade	Couping	Burst	Collapse	Tension	
Surface casing	0'	300'	24.0	J-55	STC	2,950	1,370	244,000	
8-5/8"	U	300	24.0	3-33	5	17.53	14.35	33.89	
Prod casing	0'	6 F07'	15.5	J-55	LTC	4,810	4,040	217,000	
5-1/2"	U	6,597'	10.5	J-55	LIC	2.29	1.92	2.12	

#### Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg
Pore pressure at surface casing shoe = 8.33 ppg
Pore pressure at prod casing shoe = 8.33 ppg
Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. Cementing Design: GMBU U-33-8-16

Job	Fill	Description	Sacks ft <sup>3</sup>	OH Excess*	Weight (ppg)	Yield (ft³/sk)
Surface casing	300'	Class G w/ 2% CaCl	138	30%	15.8	1.17
- Curiado dading	000	51000 5 W 270 5001	161	0070	10.0	,
Prod casing	4,597'	Prem Lite II w/ 10% gel + 3%	318	30%	11.0	3.26
Lead	4,597	KCI	1035	30 //	11.0	3.20
Prod casing	2,000'	50/50 Poz w/ 2% gel + 3%	363	30%	14.3	1.24
Tail	2,000	KCI	451	30 /6	14.5	1.24

<sup>\*</sup>Actual volume pumped will be 15% over the caliper log

- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
- Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

#### 5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to Exhibit C for a diagram of BOP equipment that will be used on this well.

#### 6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

From surface to  $\pm 350$  feet will be drilled with an air/mist system. The air rig is equipped with a 6 ½" blooie line that is straight run and securely anchored. The blooie line is used with a discharge less than 100 ft from the wellbore in order to minimize the well pad size. The blooie line is not equipped with an automatic igniter or continuous pilot light and the compressor is located less than 100 ft from the well bore due to the low possibility of combustion with the air dust mixture. The trailer mounted compressor (capacity of 2000 CFM) has a safety shut-off valve which is located 15 feet from the air rig. A truck with 70 bbls of water is on stand by to be used as kill fluid, if necessary. From about  $\pm 350$  feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

#### 7. <u>AUXILIARY SAFETY EQUIPMENT TO BE USED</u>:

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

#### 8. <u>TESTING, LOGGING AND CORING PROGRAMS</u>:


The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 300' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +-. A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.


#### 9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:


No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.


#### 10. <u>ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:</u>


It is anticipated that the drilling operations will commence the third quarter of 2011, and take approximately seven (7) days from spud to rig release.












	43013506940	000	1		1.	1	5/ =	1 2	1 11	1 = 1	2 1			
	8	D P		я	, 5		//	d e	1.2		я	+		
	Graft Wells Graft Wells Gutter Sand Orders Photochy Gas this Photochy Gas this Frobering Gas this	Cry thom.  Terrocarrich Abanthanat Filtightid & Abandoned Shar in Without Source Well	though the same of	В	<i>U.</i>	1.16	1	4		s (			i	
	Mendent V45/IS Localin Surface Smol Oritina Visiting on Comple Visiting on Comple Froducing On Van Froducing On Van Visitin Pripage Sea Man Visitin Pr	Source A	Principal Stafform		+3			-	8	a	a	NEWFIELD	Edribit A	
	Graft William Surface Costing Vanding Producting Produc	Temporary Physimal Shrein Wheter Se	Mile Dutants	5 s		7	. +	13° 13°	T.			W. KY MILL	Eda	
	N. 1 . 1	-+	- 2 CM	41 4	1/		4.		F.			Z E	E	
				C	1243	12 -		2	8	R	ñ			
	. 2 2	*	10	8 1		1	4		1		Ĺ			Ima
		+		-	A Profit		2	• 5	2	10	7.	1 .		
	w E 5	4	R	n Z	4-5	0 4 9	+#	11	-	<u>\$</u>	-		+	
			-		1 composition			2 41	2 27	ž.	8			0
	n 9 P	п	1	2 44			4 4		-	ļ		-	1,2	_
		22		- 4	Ties.	43.43		2	E R	4	, x			2
		S .	Æ	R/50	LK.	""	1 2	1350	4		4		-	
		= =	-	[85-R	1 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	· · · · · · · · · · · · · · · · · · ·	भी साम मूं <del>।</del> यं का व्य	लं व	3	-1		· ·	TEST	01
			1	Tess Tess	4. 44	120 el e	3 02 01 +5+	ન ક્યુ	= =	5 c u	Ł.		-	
		£	1 -	41 19	ने जुन म जुन म	4 4 /74	5 m m 13 m			40.3.4				
		1	-/.		et 25 482.7	19 12 4	हिंद्दत्तु प् चिंदत्तु प्	15 1	中学	14 mg - 2	#	*		17
	u . 5		1 Bi 4	4 1 R 47		4 725	र वा वा व	ej e	if et et	3 03	-	-	-	_
			8	4,	44.4	है दे जब न	ର ପ ମ ଧ		4 4 44	2	76	*		î
	. 2 2	z.4	7 1 E	1 83 3	d Fig.	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	10 00 03 02	·3	f ef ef ef .		3		-	-
		-4	15 15 4 50 at	100	API 4 A	in a di	भाग चर्च वा चर्च	ण गाँ व व मं <del>१३</del> १३१	नेन पर च च च च	** n	1 1	-	1	-
		a	E 1-12	80 30	The state of the s	है क प्रश्ति १ वस्तु १	न न वह	4 1	स्तु हैता । जो	1				
	- 3	5. l. 2	10 M		9 5 to			न भी न	35					
				and i			1	4 3 -2 4 L		<u> </u>	R		ļ:	:
	n 9 E	r <sub>el</sub>	14 1 9 4 1 154 - 4 1		केशन जे. केशन जे.	1000	નું પુંચ	4 <sup>2</sup> 4 4	344				-	
		99 9		A NOT NOT A	40 300	daysu vid	3.13	ોના દેવ	130 A		a	•		4
		4.4	1 3 4	NI S		0 V.14		A KINE	47 e3 e e3				2	_
		F 4 4	4 744 4 74 7	11/34 /	1474 7474 7474 7474	-14 4 4		444	e: ej	4 2	R		į.	Е
		• 2 7	414	<b>对对人的</b>	3 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	45° 114	THE		전면 역 <u>연락성</u> 주인	4			1-	_
	e e 2	हैं की दी की दी	101	19.02 X 8 05 10	MAN	31 (10) 1	NI THE	वस्य व प्रवास	न विश्व की नहें की व					n
10	_	र्ग ह	17 17	4.9-45 A2	MAN.	14.6	17.4	111	નું નું નું નું	ež D u()	2	( <del>31</del> 0	"	4
	e h 2	. 4	1 1 4	13.5 19.0	Airi .		4/10/	1000	न न ।।न	चंद				-
		12	4 4 4 4	4 14	1	N	1 17	4 44	4 4 4	15 R	ā:	w		Ð
	* E E	4 4 4	448	1 R 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	MALANIA	42 /105 /	i ligh	त निष्	स्य स्थाप स्थास	e) e)				-
			4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4		LARA.	1 1 11	1102	તે હે હું હું વું હું હું હું	ન નેન્ય નાનવં ને નાનવં વે ના ઓનાવ	of 2	×	- 12	2	100
Ì	n 1 2	2 6	4 4 4 4 4	19 10	1131	4 v [2]	1900	1 1 12	ej ej ej ej	45			-	-
1		44	44 40	W D	i da	ST N	1	V	संस्था स्थापना	+2	R	*	2	E
		2 40	B	4144	STO I	.T. 75	44.4	地門	·9 129 · 1	3				_
		2 40		+1/1+	NO TO	रा व व व	N. C.		777	2	90		¥	
	20	I V	п .	E	4 4 4 8	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	Sill of	12. 0 15. 5. 5. 5. 5. 5. 5. 5. 5. 5. 5. 5. 5. 5	नं नृत्यं स		1	10	=	
			1. "	20	79 Y	4 44 4	वत प्रकृत	1 12	1 44 4	3.10				
Birth			1 = #	4 1		14 12	युवन न	क्षित्र चित्र	भे न भेने सो स देखें	C.	8	1		
	6 5	E 1	1-2 -12	1.1	- d-		पर्वत ने	गर्ग-	7 7 7 7	==				
		•5	4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	R 10 18		CS	त्रव नंग	4 4 4	4 50	E E	*	0		
	s	er en	R =4 =5	C R	40 4V	प्तप्त	Cara Ca	177	4) 44 44					_
1				RE	* 3	1 300		44	4 4 4	R CO	F.	o:	*	
1	- 0 0	2	× 1	3 8		1 2 4 1	V4 12		3 0 2 5	14 5				
1				50	4 11	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	N. W.	12.5	111	क्य व	2		2	
100			. \	21	"	TE	T. T. T.	2 . 4 1	770 B B	S Max all Di			4	_
la.	* * * * * * * * * * * * * * * * * * *	B	n t	E		2000	Vel / 4	199	9 4 9 43	4 4	R	. 9		
-	2 2				00	The state of	14 V 4 V 4 V 4 V 4 V 4 V 4 V 4 V 4 V 4 V	3101	प्रमु रहेन	7 1 4 4		3 3		
K	2 2 -	2	2	R	•	9	जिस्से द	1.10	9-9 14	19 4		H		
11	* 0 2				-	6	2	121	194	2 2 2 2	x		2	
1	e e 2	7.	R	R		-	•	7	n	2 2 1	-	-	2 6	=





## **NEWFIELD EXPLORATION**

USGS Myton SW (UT) SECTION 3 T9S, R16E U-33-8-16

Wellbore #1

Plan: Design #1

# **Standard Planning Report**

22 April, 2011





#### PayZone Directional Services, LLC.

**Planning Report** 



Database: EDM 2003.21 Single User Db Company: NEWFIELD EXPLORATION Project: USGS Myton SW (UT) Site: SECTION 3 T9S, R16E

 Well:
 U-33-8-16

 Wellbore:
 Wellbore #1

 Design:
 Design #1

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well U-33-8-16

U-33-8-16 @ 5672.0ft (Original Well Elev) U-33-8-16 @ 5672.0ft (Original Well Elev)

True

Minimum Curvature

Project USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA

Map System: US State Plane 1983

Geo Datum: North American Datum 1983

Map Zone: Utah Central Zone

System Datum: Mean Sea Level

Site SECTION 3 T9S, R16E

Northing: 7,193,000.00 ft Site Position: Latitude: 40° 3' 29.861 N From: Мар Easting: 2,030,700.00 ft Longitude: 110° 6' 20.047 W **Position Uncertainty:** 0.0 ft Slot Radius: **Grid Convergence:** 0.89 °

Well U-33-8-16, SHL LAT: 40 03 54.11 LONG: -110 06 43.90

 Well Position
 +N/-S
 2,453.5 ft
 Northing:
 7,195,424.45 ft
 Latitude:
 40° 3′ 54.110 N

 +E/-W
 -1,854.6 ft
 Easting:
 2,028,807.60 ft
 Longitude:
 110° 6′ 43.900 W

Position Uncertainty 0.0 ft Wellhead Elevation: 5,672.0 ft Ground Level: 5,660.0 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	2010/12/02	11.40	65.82	52,326

Design	Design #1					
Audit Notes:						
Version:		Phase:	PROTOTYPE	Tie On Depth:	0.0	
Vertical Section:		Depth From (TVD)	+N/-S	+E/-W	Direction	
		(ft)	(ft)	(ft)	(°)	
		0.0	0.0	0.0	314.45	

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,644.1	15.66	314.45	1,631.1	99.3	-101.2	1.50	1.50	0.00	314.45	
5,142.8	15.66	314.45	5,000.0	760.7	-775.5	0.00	0.00	0.00	0.00	U-33-8-16 TGT
6,596.8	15.66	314.45	6,400.0	1,035.6	-1,055.6	0.00	0.00	0.00	0.00	



#### PayZone Directional Services, LLC.

Planning Report



Database: EDM 2003.21 Single User Db Company: NEWFIELD EXPLORATION Project: USGS Myton SW (UT) Site: SECTION 3 T9S, R16E

 Well:
 U-33-8-16

 Wellbore:
 Wellbore #1

 Design:
 Design #1

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well U-33-8-16

U-33-8-16 @ 5672.0ft (Original Well Elev) U-33-8-16 @ 5672.0ft (Original Well Elev)

True

Minimum Curvature

Design:	Design #1								
Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	1.50	314.45	700.0	0.9	-0.9	1.3	1.50	1.50	0.00
800.0	3.00	314.45	799.9	3.7	-3.7	5.2	1.50	1.50	0.00
900.0	4.50	314.45	899.7	8.2	-8.4	11.8	1.50	1.50	0.00
1,000.0	6.00	314.45	999.3	14.6	-14.9	20.9	1.50	1.50	0.00
1,100.0	7.50	314.45	1,098.6	22.9	-23.3	32.7	1.50	1.50	0.00
1,200.0	9.00	314.45	1,197.5	32.9	-33.6	47.0	1.50	1.50	0.00
1,300.0	10.50	314.45	1,296.1	44.8	-45.7	64.0	1.50	1.50	0.00
1,400.0	12.00	314.45	1,394.2	58.4	-59.6	83.5	1.50	1.50	0.00
1,500.0	13.50	314.45	1,491.7	73.9	-75.3	105.5	1.50	1.50	0.00
1,600.0	15.00	314.45	1,588.6	91.1	-92.9	130.2	1.50	1.50	0.00
1,644.1	15.66	314.45	1,631.1	99.3	-101.2	141.8	1.50	1.50	0.00
1,700.0	15.66	314.45	1,685.0	109.9	-112.0	156.9	0.00	0.00	0.00
1,800.0	15.66	314.45	1,781.3	128.8	-131.3	183.9	0.00	0.00	0.00
1,900.0	15.66	314.45	1,877.5	147.7	-150.5	210.9	0.00	0.00	0.00
2,000.0	15.66	314.45	1,973.8	166.6	-169.8	237.9	0.00	0.00	0.00
2,100.0	15.66	314.45	2,070.1	185.5	-189.1	264.9	0.00	0.00	0.00
2,200.0	15.66	314.45	2,166.4	204.4	-208.4	291.9	0.00	0.00	0.00
2,300.0	15.66	314.45	2,262.7	223.3	-227.6	318.9	0.00	0.00	0.00
2,400.0	15.66	314.45	2,359.0	242.2	-246.9	345.9	0.00	0.00	0.00
2,500.0	15.66	314.45	2,455.3	261.1	-266.2	372.9	0.00	0.00	0.00
2,600.0	15.66	314.45	2,551.6	280.0	-285.4	399.9	0.00	0.00	0.00
2,700.0	15.66	314.45	2,647.8	298.9	-304.7	426.8	0.00	0.00	0.00
2,800.0	15.66	314.45	2,744.1	317.8	-324.0	453.8	0.00	0.00	0.00
2,900.0	15.66	314.45	2,840.4	336.7	-343.3	480.8	0.00	0.00	0.00
3,000.0	15.66	314.45	2,936.7	355.6	-362.5	507.8	0.00	0.00	0.00
3,100.0	15.66	314.45	3,033.0	374.5	-381.8	534.8	0.00	0.00	0.00
3,200.0 3,300.0	15.66 15.66	314.45 314.45	3,129.3 3,225.6	393.4 412.3	-401.1 -420.3	561.8 588.8	0.00 0.00	0.00 0.00	0.00 0.00
3,400.0 3,500.0	15.66	314.45	3,321.9	431.2	-439.6	615.8	0.00	0.00	0.00
-,	15.66 15.66	314.45	3,418.1	450.1 460.0	-458.9 478.1	642.8	0.00	0.00	0.00
3,600.0	15.66 15.66	314.45 314.45	3,514.4 3,610.7	469.0 488.0	-478.1 -497.4	669.8 696.8	0.00 0.00	0.00	0.00 0.00
3,700.0 3,800.0	15.66	314.45	3,707.0	506.9	-497.4 -516.7	723.8	0.00	0.00 0.00	0.00
3,900.0	15.66	314.45	3,803.3	525.8	-536.0	750.8	0.00	0.00	0.00
4,000.0	15.66	314.45	3,899.6	544.7	-555.2	777.8	0.00	0.00	0.00
4,100.0	15.66	314.45	3,995.9	563.6	-574.5	804.8	0.00	0.00	0.00
4,200.0	15.66	314.45	4,092.2	582.5	-593.8	831.8	0.00	0.00	0.00
4,300.0	15.66	314.45	4,188.4	601.4	-613.0	858.8	0.00	0.00	0.00
4,400.0	15.66	314.45	4,284.7	620.3	-632.3	885.8	0.00	0.00	0.00
4,500.0	15.66	314.45	4,381.0	639.2	-651.6	912.8	0.00	0.00	0.00
4,600.0	15.66	314.45	4,477.3	658.1	-670.8	939.7	0.00	0.00	0.00
4,700.0	15.66	314.45	4,573.6	677.0	-690.1	966.7	0.00	0.00	0.00
4,800.0	15.66	314.45	4,669.9	695.9	-709.4	993.7	0.00	0.00	0.00
4,900.0	15.66	314.45	4,766.2	714.8	-728.7	1,020.7	0.00	0.00	0.00
5,000.0	15.66	314.45	4,862.5	733.7	-747.9	1,047.7	0.00	0.00	0.00
5,100.0	15.66	314.45	4,958.7	752.6	-767.2	1,074.7	0.00	0.00	0.00
5,142.8	15.66	314.45	5,000.0	760.7	-775.5	1,086.3	0.00	0.00	0.00



#### PayZone Directional Services, LLC.

Planning Report



Database: EDM 2003.21 Single User Db Company: NEWFIELD EXPLORATION Project: USGS Myton SW (UT)
Site: SECTION 3 T9S, R16E

 Well:
 U-33-8-16

 Wellbore:
 Wellbore #1

 Design:
 Design #1

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well U-33-8-16

U-33-8-16 @ 5672.0ft (Original Well Elev) U-33-8-16 @ 5672.0ft (Original Well Elev)

True

Minimum Curvature

ed Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
U-33-8-16 TO	<b>ST</b>								
5,200.0	15.66	314.45	5,055.0	771.5	-786.5	1,101.7	0.00	0.00	0.00
5,300.0	15.66	314.45	5,151.3	790.4	-805.7	1,128.7	0.00	0.00	0.00
5,400.0	15.66	314.45	5,247.6	809.3	-825.0	1,155.7	0.00	0.00	0.00
5,500.0	15.66	314.45	5,343.9	828.2	-844.3	1,182.7	0.00	0.00	0.00
5,600.0	15.66	314.45	5,440.2	847.1	-863.5	1,209.7	0.00	0.00	0.00
5,700.0	15.66	314.45	5,536.5	866.0	-882.8	1,236.7	0.00	0.00	0.00
5,800.0	15.66	314.45	5,632.8	884.9	-902.1	1,263.7	0.00	0.00	0.00
5,900.0	15.66	314.45	5,729.0	903.8	-921.4	1,290.7	0.00	0.00	0.00
6,000.0	15.66	314.45	5,825.3	922.7	-940.6	1,317.7	0.00	0.00	0.00
6,100.0	15.66	314.45	5,921.6	941.6	-959.9	1,344.7	0.00	0.00	0.00
6,200.0	15.66	314.45	6,017.9	960.6	-979.2	1,371.7	0.00	0.00	0.00
6,300.0	15.66	314.45	6,114.2	979.5	-998.4	1,398.7	0.00	0.00	0.00
6,400.0	15.66	314.45	6,210.5	998.4	-1,017.7	1,425.6	0.00	0.00	0.00
6,500.0	15.66	314.45	6,306.8	1,017.3	-1,037.0	1,452.6	0.00	0.00	0.00
6,596.8	15.66	314.45	6,400.0	1,035.6	-1,055.6	1,478.8	0.00	0.00	0.00




Project: USGS Myton SW (UT) Site: SECTION 3 T9S, R16E

Well: U-33-8-16 Wellbore: Wellbore #1 Design: Design #1

Azimuths to True North Magnetic North: 11.40°


Magnetic Field Strength: 52325.8snT Dip Angle: 65.82° Date: 2010/12/02 Model: IGRF2010

KOP @ 600' DOGLEG RATE 1.5 DEG/100 TARGET RADIUS IS 75'









SECTION DETAILS Azi +N/-S +E/-W DLeg VSec Target 0.0 600.0 1631.1 0.0 0.0 141.8 0.0 0.00 0.00 0.0 0.0 0.00 0.00 600.0 0.00 0.00 1644.1 15.66 314.45 0.0 99.3 0.0 -101.2 0.00 0.00 1.50 314.45 15.66 314.45 5000.0 760.7 -775.5 0.00 0.00 1086.3 U-33-8-16 TGT 6596.8 15.66 314.45 6400.0 1035.6 -1055.6

# NEWFIELD PRODUCTION COMPANY GMBU U-33-8-16 AT SURFACE: NW/NW (LOT #4) SECTION 3, T9S, R16E DUCHESNE COUNTY, UTAH

#### ONSHORE ORDER NO. 1

#### **MULTI-POINT SURFACE USE & OPERATIONS PLAN**

#### 1. EXISTING ROADS

See attached Topographic Map "A"

To reach Newfield Production Company well location site GMBU U-33-8-16 located in the NW 1/4 NW 1/4 Section 3, T9S, R16E, Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.4 miles  $\pm$  to the junction of this highway and UT State Hwy 53; proceed southeasterly – 6.2 miles  $\pm$  to it's junction with an existing dirt road to the southwest; proceed in a southwesterly direction – 3.8 miles  $\pm$  to it's junction with an existing road to the south; proceed southerly – 0.5 miles  $\pm$  to the existing 4-3-9-16 well location.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

#### 2. PLANNED ACCESS ROAD

There is no proposed access road for this location. The proposed well will be drilled directionaly off of the existing 4-3-9-16 well pad. See attached **Topographic Map "B"**.

There will be **no** culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

#### 3. <u>LOCATION OF EXISTING WELLS</u>

Refer to Exhibit "B".

#### 4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

#### 5. LOCATION AND TYPE OF WATER SUPPLY

Newfield Production will transport water by truck from nearest water source as determined by a Newfield representative for the purpose of drilling the above mentioned well. The available water sources are as follows:

Johnson Water District Water Right: 43-10136

Maurice Harvey Pond Water Right: 47-1358

Neil Moon Pond Water Right: 43-11787

Newfield Collector Well

Water Right: 47-1817 (A30414DVA, contracted with the Duchesne County Conservancy

District).

There will be no water well drilled at this site.

#### 6. SOURCE OF CONSTRUCTION MATERIALS

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

#### 7. METHODS FOR HANDLING WASTE DISPOSAL

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

#### 8. ANCILLARY FACILITIES

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

#### 9. <u>WELL SITE LAYOUT</u>

See attached Location Layout Sheet.

#### **Fencing Requirements**

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

#### 10. PLANS FOR RESTORATION OF SURFACE:

#### a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

#### b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

#### 11. <u>SURFACE OWNERSHIP</u> – Bureau of Land Management.

#### 12. OTHER ADDITIONAL INFORMATION

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. MOAC Report #11-051, 4/8/11. Paleontological Resource Survey prepared by, Wade E. Miller, 4/23/11. See attached report cover pages, Exhibit "D".

Newfield Production Company requests 60' of buried water line to be granted in Lease UTU-77338.

It is proposed that the disturbed area will be 30' wide to allow for construction of the proposed buried 10" steel water injection line and a buried 3" poly water return line. The proposed buried water lines will tie in to the existing pipeline infrastructure. **Refer to Topographic Map "C."** The proposed water pipelines will be buried in a 4-5' deep trench constructed with a trencher or backhoe for the length of the proposal. The equipment will run on the surface and not be flat bladed to minimize surface impacts to precious topsoil in these High Desert environments. If possible, all proposed surface gas pipelines will be installed on the same side of the road as existing gas lines. The construction phase of the proposed water lines will last approximately (5) days.

In the event that the proposed well is converted to a water injection well, a Sundry Notice 3160-5 form will be applied for through the Bureau of Land Management field office.

#### Water Disposal

After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.

#### **Additional Surface Stipulations**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

#### **Details of the On-Site Inspection**

The proposed GMBU U-33-8-16 was on-sited on 1/26/11. The following were present; Tim Eaton (Newfield Production), Janna Simonsen (Bureau of Land Management), and Suzanne Grayson (Bureau of Land Management).

#### **Hazardous Material Declaration**

Newfield Production Company guarantees that during the drilling and completion of the GMBU U-33-8-16, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the GMBU U-33-8-16, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

#### 13. <u>LESSEE'S OR OPERATOR'S REPRENSENTATIVE AND CERTIFICATION:</u>

Representative

Name: Tim Eaton

Address: Newfield Production Company

Route 3, Box 3630 Myton, UT 84052

Telephone: (435) 646-3721

#### Certification


Please be advised that NEWFIELD PRODUCTION COMPANY is considered to be the operator of well #U-33-8-16, Section 3, Township 9S, Range 16E: Lease UTU-77338 Duchesne County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by, Federal Bond #WYB000493.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.


4/27/11	
Date	Mandie Crozie
	Regulatory Specialis
	Newfield Production Company


2-M SYSTEM

**Blowout Prevention Equipment Systems** 



**EXHIBIT C** 







CROSS SECTIONS


X-34-8-16 (Proposed Well)


U-33-8-16 (Proposed Well)

4-3-9-16 (Existing Well)

Pad Location: NWNW (Lot 4) Section 3, T9S, R16E, S.L.B.&M.









1'' = 50' STA. 0+30

ESTIMATED EARTHWORK QUANTITIES
(No Shrink or swell adjustments have been used)
(Expressed in Cubic Yards)

ITEM CUT FILL 6" TOPSOIL EXCESS
PAD 300 10 Topsoil is 290

NOTE: UNLESS OTHERWISE NOTED CUT SLOPES ARE AT 1:1 FILL SLOPES ARE AT 1.5:1

PAD 300 10 Topsoil is 290 not included in included	ITEM	CUT	FILL	6" TOPSOIL	EXCESS
	PAD	300	10		290
P11   640   0   in Pad Cut   640	PIT	640	0	in Pad Cut	640
TOTALS 940 10 140 930	TOTALS	940	10	140	930

SURVEYED BY: D.G.	DATE SURVEYED:	10-06-10
DRAWN BY: M.W.	DATE DRAWN:	12-06-10
SCALE: $1" = 50'$	REVISED:	

 $egin{array}{lll} egin{array}{lll} Tri & State & ^{(435)} & ^{781-2501} \ & Land & Surveying, & Inc. \ & \_\_\_\_ & 180 & NORTH & VERNAL & AVE. & VERNAL, & UTAH & B4078 \ \end{array}$ 

### NEWFIELD EXPLORATION COMPANY TYPICAL RIG LAYOUT X-34-8-16 (Proposed Well) U-33-8-16 (Proposed Well) 4-3-9-16 (Existing Well) Pad Location: NWNW (Lot 4) Section 3, T9S, R16E, S.L.B.&M. YELLOW DOG Existing Anchor (Typ.) BOILER 22 PUMP STORAGE TANK PUMP HOUSE 15' RESERVE PIT (8' Deep) 86' 29 FUEL Pump Jack PIPE RACKS ☐ TOILET PIPE RACKS TRAILERS Seperator 57 Existing Tanks DATA Existing SURVEYED BY: Tri~State (435) 781—Land~Surveying,~Inc. 180 NORTH VERNAL AVE. VERNAL, UTAH 84078 D.G. DATE SURVEYED: 10-06-10 (435) 781-2501 DRAWN BY: M.W. DATE DRAWN: 12-06-10 1" = 50' SCALE: REVISED:

### **United States Department of the Interior**

#### BUREAU OF LAND MANAGEMENT

Utah State Office P.O. Box 45155 Salt Lake City, Utah 84145-0155

IN REPLY REFER TO: 3160 (UT-922)

April 29, 2011

#### Memorandum

To: Assistant District Manager Minerals, Vernal District

Michael Coulthard, Petroleum Engineer From:

2011 Plan of Development Greater Monument

Butte Unit, Duchesne and Uintah Counties,

Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2011 within the Greater Monument Butte Unit, Duchesne and Uintah Counties, Utah.

API#	WELL NAME			LOCATION						
43-013-50692	GMBU					R16E R16E		_		
43-013-50693	GMBU					R15E R15E				
43-013-50694	GMBU					R16E R16E				FWL FEL
43-013-50695	GMBU					R16E R16E				
43-013-50696	GMBU					R16E R16E		_		
43-013-50697	GMBU					R16E R16E				
43-013-50698	GMBU					R16E R16E				
43-013-50700	GMBU					R16E R16E				

Page 2

API#	WELL NAME			LOCATION						
43-013-50701	GMBU					R16E R16E		_		FWL FWL
43-013-50702	GMBU					R16E R16E		_		
43-013-50703	GMBU					R16E R16E				
43-013-50704	GMBU					R16E R16E		_		
43-013-50705	GMBU					R16E R16E		_		
43-013-50706	GMBU					R16E R16E				FEL FWL

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L. Coulthard


DN: cn=Michael L. Coulthard, o=Bureau of Land

Management, ou=Branch of Minerals,
email=Michael\_Coulthard@blm.gov, c=US

Date: 2011.04.29 11:12:00 -06'00'

bcc: File - Greater Monument Butte Unit Division of Oil Gas and Mining Central Files Agr. Sec. Chron Fluid Chron

MCoulthard:mc:4-29-11





#### VIA ELECTRONIC DELIVERY

May 11, 2011

State of Utah, Division of Oil, Gas and Mining ATTN: Diana Mason P.O. Box 145801 Salt Lake City, UT 84114-5801

RE:

Directional Drilling

GMBU U-33-8-16

Greater Monument Butte (Green River) Unit

Surface Hole:

T9S-R16E Section 3: NWNW (Lot #4) (UTU-77338)

782' FNL 769' FWL

At Target:

T8S-R16E Section 33: SESE (UTU-49092)

269' FSL 265' FEL

Duchesne County, Utah

Dear Ms. Mason:

Pursuant to the filing by Newfield Production Company (NPC) of an Application for Permit to Drill the above referenced well dated 4/28/11, a copy of which is attached, and in accordance with Oil and Gas Conservation Rule R649-3-11, NPC hereby submits this letter as notice of our intention to directionally drill this well.

The surface hole and target locations of this well are both within the boundaries of the Greater Monument Butte Unit (UTU-87538X), of which Newfield certifies that it is the operator. Further, Newfield certifies that all lands within 460 feet of the entire directional well bore are within the Greater Monument Butte Unit.

NPC is permitting this well as a directional well in order to mitigate surface disturbance by utilizing preexiting roads and pipelines.


NPC hereby requests our application for permit to drill be granted pursuant to R649-3-11. If you have any questions or require further information, please contact the undersigned at 303-383-4197 or by email at sgillespie@newfield.com. Your consideration in this matter is greatly appreciated.


Sincerely,


Newfield Production Company

Shane Gillespie Land Associate

Form 3160 - 3 (August 2007)	FORM APPROVED OMB No. 1004-0137 Expires July 31, 2010						
UNITED STATES DEPARTMENT OF THE I BUREAU OF LAND MAN.	5. Lease Serial No. UTU-77338						
APPLICATION FOR PERMIT TO	6. If Indian, Allotee or Tribe Name NA						
la. Type of work:  DRILL  REENTE	7 If Unit or CA Agreement, Name and No. Greater Monument Butte						
Ib. Type of Well:  Oil Well  Gas Well Other	8, Lease Name and Well No. GMBU U-33-8-16						
Name of Operator Newfield Production Company			9 API Well No.				
3a. Address Route #3 Box 3630, Myton UT 84052	3b. Phone No. (include area co (435) 646-3721						
4. Location of Well (Report location clearly and in accordance with any	•		11. Sec., T. R. M. or B	lk. and Survey or Area			
Al surface NW/NW (LOT #4) 782' FNL 769' FWL Sec.	Sec. 3, T9S R16E						
At proposed prod. zonc SE/SE 269' FSL 265' FEL Sec. 3:	12 County or Parish	13. State					
14 Distance in miles and direction from nearest town or post office* Approximately 11.9 miles southwest of Myton, UT			Duchesne	UT			
15 Distance from proposed* location to nearest	16. No. of acres in lease	17 Spacin	ing Unit dedicated to this well				
property or lease line, ft. Approx. 265' f/lse, NA f/unit (Also to nearest drig. unit line, if any)	520.84		20 Acres				
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.  Approx. 792'	19. Proposed Depth 6,597'	12520 PRO-00000	/BIA Bond No. on file WYB000493				
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5660' GL	22. Approximate date work w	ill start*	23. Estimated duration (7) days from SPUD to rig release				
	24. Attachments						
The following, completed in accordance with the requirements of Onshore	e Oil and Gas Order No.1, mus	t be attached to th	is form:				
<ol> <li>Well plat certified by a registered surveyor.</li> <li>A Drilling Plan.</li> </ol>	Item 20 ab	ove).	ns unless covered by an	existing bond on file (see			
<ol> <li>A Surface Use Plan (if the location is on National Forest System L SUPO must be filed with the appropriate Forest Service Office).</li> </ol>	formation and/or plans as may be required by the						
25 Signature Marrole Crossin	Name (Printed Typed) Mandie Crozier		Date (1/38/1)				
Title Regulatory Specialist							
Approved by (Signature)	Name (Printed Typed)			Date			
Title	Office	Office					
Application approval does not warrant or certify that the applicant holds conduct operations thereon.  Conditions of approval, if any, are attached.	legal or equitable title to those	e rights in the sub	ject lease which would e	ntitle the applicant to			
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a cristates any false, fictitious or fraudulent statements or representations as to	me for any person knowingly any matter within its jurisdiction	and willfully to m on.	ake to any department o	r agency of the United			
(Continued on page 2)			*(Inst	ructions on page 2)			







#### WORKSHEET APPLICATION FOR PERMIT TO DRILL

**APD RECEIVED:** 4/27/2011 **API NO. ASSIGNED:** 43013506940000

WELL NAME: GMBU U-33-8-16

**PHONE NUMBER:** 435 646-4825 **OPERATOR:** NEWFIELD PRODUCTION COMPANY (N2695)

**CONTACT:** Mandie Crozier

PROPOSED LOCATION: NWNW 03 090S 160E **Permit Tech Review:** 

> **SURFACE:** 0782 FNL 0769 FWL **Engineering Review:**

> BOTTOM: 0269 FSL 0265 FEL Geology Review:

**COUNTY: DUCHESNE** 

**LATITUDE: 40.06498 LONGITUDE:** -110.11147 **UTM SURF EASTINGS: 575775.00 NORTHINGS:** 4435137.00

FIELD NAME: MONUMENT BUTTE

LEASE TYPE: 1 - Federal

**LEASE NUMBER:** UTU-77338 PROPOSED PRODUCING FORMATION(S): GREEN RIVER SURFACE OWNER: 1 - Federal **COALBED METHANE: NO** 

**RECEIVED AND/OR REVIEWED: LOCATION AND SITING:** 

 PLAT R649-2-3.

Unit: GMBU (GRRV) Bond: FEDERAL - WYB000493

**Potash** R649-3-2. General

Oil Shale 190-5

Oil Shale 190-3 R649-3-3. Exception

Oil Shale 190-13 **Drilling Unit** 

Board Cause No: Cause: 213-11 Water Permit: 437478

**Effective Date:** 11/30/2009 **RDCC Review:** 

Siting: Suspends General Siting **Fee Surface Agreement** 

**Intent to Commingle** ■ R649-3-11. Directional Drill

**Commingling Approved** 

**Comments:** Presite Completed

Stipulations: 4 - Federal Approval - dmason

15 - Directional - dmason 27 - Other - bhill

API Well No: 43013506940000



# State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

# Permit To Drill

\*\*\*\*\*\*

Well Name: GMBU U-33-8-16
API Well Number: 43013506940000
Lease Number: UTU-77338

Surface Owner: FEDERAL Approval Date: 5/11/2011

#### **Issued to:**

NEWFIELD PRODUCTION COMPANY, Rt 3 Box 3630, Myton, UT 84052

#### **Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause: 213-11. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

#### **Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

#### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

### **Conditions of Approval:**

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Production casing cement shall be brought up to or above the top of the unitized interval for the Greater Monument Butte Unit (Cause No. 213-11).

### **Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

• Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please leave a voicemail message if not available)
OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at http://oilgas.ogm.utah.gov

API Well No: 43013506940000

# **Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) due prior to implementation
- Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
- Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

**Approved By:** 

For John Rogers Associate Director, Oil & Gas Form 3160-3 (August 2007)

# APR 2 9 2011

### FORM APPROVED OMB No. 1004-0137 Expires July 31, 2010

#### UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

Lease Serial No. UTU-77338

APPLICATION FOR PERMIT TO	DRILL OR REENTER		6. If Indian, Allotee or T	ribe Name
la. Type of work:	ER		7. If Unit or CA Agreemer Greater Monument	•
lb. Type of Well: Oil Well Gas Well Other	✓ Single Zone Multi	ole Zone	8. Lease Name and Well 3 GMBU U-33-8-16	No.
Name of Operator Newfield Production Company		İ	9. API Well No. 43-013-5	0694
3a. Address Route #3 Box 3630, Myton UT 84052	3b. Phone No. (include area code)		10. Field and Pool, or Explo	ratory
	(435) 646-3721		Monument Butte	
4. Location of Well (Report location clearly and in accordance with an	ty State requirements.*)		11. Sec., T. R. M. or Blk.an	d Survey or Area
At surface NW/NW (LOT #4) 782' FNL 769' FWL Sec	:. 3, T9S R16E (UTU-77338)		Sec. 3, T9S R16E	
At proposed prod. zone SE/SE 269' FSL 265' FEL Sec. 3	33, T8S R16E (UTU-49092)			
<ol> <li>Distance in miles and direction from nearest town or post office*</li> <li>Approximately 11.9 miles southwest of Myton, UT</li> </ol>			12. County or Parish  Duchesne	13. State
15. Distance from proposed*	16. No. of acres in lease	17. Spacing	Unit dedicated to this well	
location to nearest property or lease line, ft. Approx. 265' f/lse, NA f/unit (Also to nearest drig. unit line, if any)	520.84		20 Acres	
18. Distance from proposed location*	19. Proposed Depth	20. BLM/B	IA Bond No. on file	
to nearest well, drilling, completed, applied for, on this lease, ft.  Approx. 792'	6,597'	w	YB000493	
21. Elevations (Show whether DF, KDB, RT, GL, etc.)	22. Approximate date work will sta	rt*	23. Estimated duration	
5660' GL	3 the Ort. 201	1	(7) days from SPUD to	rig release
	24. Attachments			

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- 1. Well plat certified by a registered surveyor.
- 2. A Drilling Plan.
- 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the

25. Signature / Canadio Crosin	Name (Printed/Typed)  Mandie Crozier	Date 4/28/11
Title  Begulatory Specialist		
Approved by (Signature)	Name (Printed/Typed)	AUG 2 5 2011
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFIC	) <b>E</b>
Application approval does not warrant or certify that the applicant h	holds legal or equitable title to those rights in the subject lease which	would entitle the applicant to

conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

RECEIVED

SEP 0 6 2011

NOS 12/28/10

DIV. OF OIL, GAS & MINING

AFMSS# 115x50200A

NOTICE OF APPROVAL

CONDITIONS OF APPROVAL ATTACHED



# UNITED STATES DEPARTMENT OF THE INTERIOR **BUREAU OF LAND MANAGEMENT** VERNAL FIELD OFFICE



(435) 781-4400



# CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company:	Newfield Production Company	Location:	NWNW, Sec. 3, T9S, R16E, SLM
Well No:	GMBU U-33-8-16	Lease No:	UTU-77338
API No:	43-013-50694	Agreement:	Greater Monument Butte Unit

**OFFICE NUMBER:** 

170 South 500 East

(435) 781-4400

OFFICE FAX NUMBER: (435) 781-3420

# A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR FIELD REPRESENTATIVE TO INSURE COMPLIANCE

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.

#### NOTIFICATION REQUIREMENTS

Location Construction (Notify Environmental Scientist)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	•	Twenty-Four (24) hours prior to running casing and cementing all casing strings to: ut vn opreport@blm.gov.
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

Page 2 of 7 Well: GMBU U-33-8-16 8/24/2011

# SURFACE USE PROGRAM CONDITIONS OF APPROVAL (COAs)

- All new and replacement internal combustion gas field engines of less than or equal to 300 designrated horsepower must not emit more than 2 gms of NO<sub>x</sub> per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO<sub>x</sub> per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop
  work and contact the Authorized Officer (AO). A determination will be made by the AO as to what
  mitigation may be necessary for the discovered paleontologic material before construction can
  continue.
- After cessation of drilling and completion operations, any visible or measurable layer of oil must be removed from the surface of the reserve pit and the pit kept free of oil.
- Pits must be free of oil and other liquid and solid wastes prior to filling. Pit liners must not be breached (cut) or filled (squeezed) while still containing fluids. The pit liner must be removed to the solids level or treated to prevent its reemergence to the surface or its interference with longterm successful revegetation.

If construction and drilling is anticipated during any of the following wildlife seasonal or spatial restrictions, a qualified consulting firm biologist must be contacted 2 weeks prior in order to conduct applicable surveys using an accepted protocol prior to any ground disturbing activities.

- Mountain plover surveys will be conducted to protocol by a professional environmental consulting
  firm biologist prior to any ground disturbing activities. Reports from survey results must be
  reviewed by a BLM authorized officer prior to proceeding with the project. A seasonal restriction
  for all ground disturbing activities in mountain plover habitat from May 1-June 15 is required.
- No construction or drilling will occur from 1/1-8/31 (.5 miles) to protect golden eagles s during the
  nesting season. If during the surveys known nests/habitat is found to be inactive, an exemption
  may be requested in writing, survey results reviewed and approved by a BLM minerals biologist
  before granting the exemption.
- Three raptor nest surveys must be conducted during the nesting season within ½ mile of the project area(s). It is recommended that these surveys be spaced 3 weeks apart, so nesting status and reproductive success can be verified and documented.
- Install hospital mufflers where possible to reduce noise impacts to wildlife.

Page 3 of 7 Well: GMBU U-33-8-16 8/24/2011

#### Reclamation

- Reclamation will be completed in accordance with the Newfield Exploration Company Castle Peak and Eight Mile Flat Reclamation Plan on file with the Vernal Field Office of the BLM.
- The reclamation seed mix will incorporate low growing grasses, instead of crested wheatgrass, which negatively impacts mountain plover habitat.
- Appropriate erosion control and revegetation measures will be employed. In areas with unstable
  soils where seeding alone may not adequately control erosion, grading will be used to minimize
  slopes and water bars will be installed on disturbed slopes. Erosion control efforts will be monitored
  by Newfield and, if necessary, modifications will be made to control erosion.

# **Monitoring and Reporting**

- The operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) that
  designates the proposed site-specific monitoring and reference sites chosen for the location. A
  description of the proposed sites shall be included, as well as a map showing the locations of the
  proposed sites.
- The operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) 3
  growing seasons after reclamation efforts have occurred evaluating the status of the reclaimed
  areas in order to determine whether the BLM standards set forth in the Green River District
  Reclamation Guidelines have been met (30% or greater basal cover).

Page 4 of 7 Well: GMBU U-33-8-16 8/24/2011

# DOWNHOLE PROGRAM CONDITIONS OF APPROVAL (COAs)

#### SITE SPECIFIC DOWNHOLE COAs:

 Newfield Production Co. shall comply with all applicable requirements in the SOP (version: "Greater Monument Butte Green River Development Program", June 24, 2008). The operator shall also comply with applicable laws and regulations; with lease terms, Onshore Oil and Gas Orders, NTL's; and with other orders and instructions of the authorized officer.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

#### DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and <u>NOT</u> by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- Cement baskets shall not be run on surface casing.
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is
  encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal
  Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB

Page 5 of 7 Well: GMBU U-33-8-16 8/24/2011

or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.

- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM,
   Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- Please submit an electronic copy of all other logs run on this well in LAS format to UT\_VN\_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

Page 6 of 7 Well: GMBU U-33-8-16 8/24/2011

#### **OPERATING REQUIREMENT REMINDERS:**

 All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.

- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at <a href="https://www.ONRR.gov">www.ONRR.gov</a>.
- Should the well be successfully completed for production, the BLM Vernal Field office must be
  notified when it is placed in a producing status. Such notification will be by written communication
  and must be received in this office by not later than the fifth business day following the date on
  which the well is placed on production. The notification shall provide, as a minimum, the following
  informational items:
  - o Operator name, address, and telephone number.
  - Well name and number.
  - Well location (¼¼, Sec., Twn, Rng, and P.M.).
  - Date well was placed in a producing status (date of first production for which royalty will be paid).
  - o The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
  - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
  - Unit agreement and/or participating area name and number, if applicable.
  - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid.)

Page 7 of 7 Well: GMBU U-33-8-16 8/24/2011

and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

 All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.

- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office
  Petroleum Engineers will be provided with a date and time for the initial meter calibration and all
  future meter proving schedules. A copy of the meter calibration reports shall be submitted to the
  BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid
  hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall
  be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering
  lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a
  suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be
  obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover
  equipment shall be removed from a well to be placed in a suspended status without prior approval
  of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior
  approval of the BLM Vernal Field Office shall be obtained and notification given before resumption
  of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

# Spud BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Ross 21 Submitted B Branden Arnold Phone Number 435-401-0223 Well Name/Number GMBU U-33-8-16 Otr/Otr NW/NW Section 3 Township 9S Range 16E Lease Serial Number UTU-77338 API Number 43-013-50694 Spud Notice — Spud is the initial spudding of the well, not drilling	
out below a casing string.	
Date/Time <u>9/29/11</u> <u>9:00</u> AM ⊠ PM □	
Casing – Please report time casing run starts, not cementing imes.  Surface Casing Intermediate Casing Production Casing Liner Other	
Date/Time <u>9/29/11</u> <u>3:00</u> AM ☐ PM ⊠	
Initial BOPE test at surface casing point BOPE test at intermediate casing point 30 day BOPE test Other	
Date/Time AM PM D	
Remarks	

FORM 3160-5 (August 2007)

# UNITED STATES DEPARTMENT OF THE INTERIOR

FORM APPROVED OMB No. 1004-0137 Expires: July 31,2010

SUNDRY Do not use the abandoned were submit in the submit	BUREAU OF LAND MANAC  / NOTICES AND REPOR his form for proposals to ell. Use Form 3160-3 (API  TRIPLICATE - Other In  Other  OMPANY  Sec., T., R., M., or Survey Descript	RTS ON WELLS drill or to re-enter an )) for such proposals structions on page 2  3b. Phone (include are 435,646,3721	USA UTU-7 6. If Indian, Al 7. If Unit or Ca GMBU  8. Well Name: GMBU U-33- 9. API Well Na 4301350694 10. Field and P GREATER N	8. Well Name and No. GMBU U-33-8-16  9. API Well No.				
Section 33 T8S R16E			DUCHESNE	E, UT				
12. CHECK	APPROPRIATE BOX(ES	) TO INIDICATE NA	ATURE OF NOTICE, OR (	OTHER DATA				
TYPE OF SUBMISSION		TYP	E OF ACTION					
Bond under which the work will be p of the involved operations. If the op Final Abandonment Notices shall be inspection.)  On 9/29/11 MIRU Ross #.	r recomplete horizontally, give subsurfaperformed or provide the Bond No. on the station results in a multiple completion of filed only after all requirements, including the state of the	ace locations and measured and file with BLM/BIA. Required or recompletion in a new inter ding reclamation, have been con- viill 315' of 12 1/4" hole	I true vertical depths of all pertinent massubsequent reports shall be filed within val, a Form 3160-4 shall be filed once impleted, and the operator has determin the with air mist. TIH W/ 7 Jt's	urkers and zones. Attach the a 30 days following completion testing has been completed. ed that the site is ready for final a 5 8 5/8" J-55 24# csgn. Set				
hereby certify that the foregoing is	true and	Title						
orrect (Printed/ Typed) Branden Arnold								
gnature	51	Date 10/05/2011						
	THIS SPACE FOR	R FEDERAL OR ST.	ATE OFFICE USE					
pproyed by ponditions of approval, if any, are attache rify that the applicant holds legal or equicant to conduct the applicant to conduct the applicant to conduct the applicant to conduct to conduct the applicant the applicant the applicant to conduct the applicant the app	uitable title to those rights in the subjec		D	oate OECEIVI				

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

OCT 1 2 2011

# **NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT**

			8 5/8"	CASING SET AT	<u></u>	313.92	_		
LAST CASING	14	SET AT	. 5	<b>,</b>	OPERATO	ıR	Newfield	Exploration	Company
DATUM				•	WELL				- Company
DATUM TO CUT			10	_	_		Monumei	nt Butte	
DATUM TO BRA	DENHEAD	FLANGE	0	<del>_</del> 		_		Ross # 26	
TD DRILLER									
HOLE SIZE									
•				-					
LOG OF CASING	STRING:								
PIECES	OD	ITEM - M	AKE - DES	CRIPTION	WT/FT	GRD	THREAD	CONDT	LENGTH
1		wellhead						Α	1.42
7	8 5/8"	casing (sh	oe jt 43.10)		24	J-55	STC	Α	303.6
1	7 5/8"	guide shoe	)					Α	0.9
							<u> </u>		
CACING INIVENIT	ODV DAL		FEET	ITO	TOTAL   F				
CASING INVENT			FEET	JTS	TOTAL LEI				305.92
TOTAL LENGTH		<del> </del>	305.92	7	LESS CUT				2
LESS NON CSG. PLUS FULL JTS.		•	2.32 0		CASING SI		UT OFF CS	G	313.92
	TOTAL		303.6	7	CASING SI	EIDEFIN			313.92
TOTAL CSG. DE		DD6)	303.0	/	} COMPA	DE			
	IMING	(NDO)			J COMPA				
BEGIN RUN CSG		Spud	9:00 AM	9/29/2011	GOOD CIR	C THRU IO	ОВ	Vac	
CSG. IN HOLE		Opud	4:00 AM	9/29/2011	1		JRFACE		
BEGIN CIRC			9:11 AM	10/4/2011	RECIPROC				
BEGIN PUMP CN	ЛT		9:25 AM	10/4/2011					
BEGIN DSPL. CN			9:37 AM		BUMPED F	LUG TO	500		

9:43 AM

10/4/2011

PLUG DOWN

STAGE	# SX	CEMENT TYPE & ADDITIVES
1	160	Class "G"+2%CaCl Mixed@ 15.8ppg W/1.17 yield returned 9bbls to pit
		HER PLACEMENT SHOW MAKE & SPACING
Middle of first, t	op of seco	nd and third for a total of three.
COMPANY REP	RESENTAT	IVE Branden Arnold DATE 10/4/2011

CEMENT COMPANY-

CEMENT USED

BJ

ADDRESS: RT. 3 BOX 3630

OPERATOR: NEWFIELD PRODUCTION COMPANY

OPERATOR ACCT. NO.

Production Clerk-

N2695

10/06/11

MYTON, UT 84052

ACTION	CURRENT ENTITY NO.	NEW	API NUMBER	WELL NAME	1		18001111	004500			
CODE	ENTITY NO.	ENTITY NO.		AATTE (ALIMIT	QQ	SC	IP IP	OCATION RG	COUNTY	SPUD DATE	EFFECTIVE DATE
В	99999	17400	4301350635	GMBU N-4-9-16	NESW	4	98	16E	DUCHESNE	10/3/2011	10/14/11
WELL 1	COMMENTS:										110/11/11
	GRRV			BHL: SW	NW						· <del></del>
ACTION CODE	CURRENT ENTITY NO	NEW ENTITY NO.	API NUMBER	WELL NAME	QQ	WEI SC	TP TP		0010071	SPUD	EFFECTIVE
В	99999	17400	4301350634	GMBU M-4-9-16	NESW	4		16E	DUCHESNE	10/4/2011	10/14/11
	GRRV			BHL= SI	· · · · · · · · · · · · · · · · · · ·	I			J J J J J J J J J J J J J J J J J J J	101-17.2011	
ACTION CODE	CURRENT ENTITY NO	NEW ENTITY NO.	API NUMBER	WELL NAME	eo.	SC 1	WELL	OGATION RG	COUNTY	SPUD DATE	EFFECTIVE
Α	99999	18259	4301350903	CONDOR TRUST 12-18-4-1W	NWSW	18	48	1W	DUCHESNE	9/30/2011	10/14/11
	GRRV									CONFIDE	
ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO	API NUMBER	WELL NAME	άQ	SC	WELL LO	DCATION RG	COUNTY	SPUD DATE	EFFECTIVE DATE
В	99999	√ 17400	4301350695	GMBU X-34-8-16	NWNW	03	95 <b>85</b>		DUCHESNE	10/1/2011	10/14/11
	GRRV			BHL Sec 3	4 78	S	St	ESI	U		
ACTION CODE	CURRENT ENTITY NO	NEW ENTITY NO.	API NUMBER	WELL NAME	QQ	sc	WELL LO	CATION RG	COUNTY	SPUD DATE	EFFECTIVE
В	99999	17 <b>4</b> 00	4301350694	GMBU U-33-8-16	NWNW	03 35	95 <b>85</b>		DUCHESNE	9/29/2011	10/14/11
	GRRV			BH : Sec	33 T	85	<u> </u>	SES	SE		
ACTION	CURRENT ENTITY NO	NEW ENTITY NO.	API NUMBER	WELL NAME	aa 1	sc	WELL LO	CATION	COUNTY	SPUD DATE	EFFECTIVE DATE
A	99999	18260	4301350876	CONDOR TRUST 6-17-4-1W	NENW	17	48		DUCHESNE	9/28/2011	10/14/11
	GRRV			BHL= SE	NW					CONFID	ENTIAL
A - 1 B - 1	CODES (See Instructions on bac new entity for new well (single w well to existing entity (group or a orn one existing entity to another	vell only) unit well)		RECEIVED					Signature	A	Jentri Park

NOTE: Use COMMENT section to explain why each Action Code was selected.

D - well from one existing entity to a new entity

E - ther (explain in comments section)

OCT 0 6 2011

DIV. OF OIL, GAS & MINING

Form 3160-4 (August 2007)

### UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED OMB NO. 1004-0137 Expires: July 31, 2010

# WELL COMPLETION OF RECOMPLETION REPORT AND LOC

	W	ELL C	OMPLET	TION OR F	RECOMPLET	TION RE	PORT	AND L	OG		5. ]	Lease Serial 1	No.	
la. Type of b. Type of	Well Completion			Gas Well Work Over	Dry Deepen D	Other Plug Back	☐ Diff	f. Resvr.,			7. <sup>1</sup>	Unit or CA A	greement	ribe Name  Name and No.
2. Name of NEWFIEL	Operator										8.	IBU (GRR) Lease Name	and Well	No.
NEWFIELI 3. Address	D EXPLO	RATION	COMPAN	1Y		3a	Phone l	No. (inclu	de area c	ode)		1BU U-33-8 AFI Well No		
			1000 DENVE			(4	435) 64E				43-	-013-50694		1
4. Location	of Well (Re	eport loca	ation clearly	and in accord	ance with Federa	ıl requiremer	nts)*					Field and Po NUMENT		oloratory
At surfac	<sup>e</sup> 782' FN	L & 769	' FWL (NW	//NW) SEC.	3, T9S, R16E (	(UTU-7733	8)				11.	Sec., T., R., Survey or A	M., on Bl rea SEC.	lock and 3, T9S, R16E
At top pro	d. interval r	eported b	elow 120'	FNL & 80' F	WL (NW/NW)	SEC. 3, T9	S, R16E	(UTU-7	7338)		<del></del>	County or P		13. State
At total de	254' F	-SL & 2	78' FEL (S	E/SE) SEC.	33, T8S, R16E	(UTU-490	192) B	HLb	HSH I	N	של	ICHESNE		UΤ
14. Date Sp 09/29/201	udded 1		15. Dat 10/26	te T.D. Reache /2011	d	16. I	Date Com	pleted 02	2/11/201 eady to Pr	1 od.	56	Elevations 60' GL 567		3, RT, GL)*
18. Total De	-	6576' D 6377		19. Ph	ig Back T.D.: N	VID 6515' IVD <b>(23)</b>	7		20. Depth	Bridge	Plug Set:	MD TVD		
21. Type E.	lectric & Oth	er Mecha	nical Logs R	un (Submit con Y,COMP. NI	oy of each) EUTRON, GR, C					well cor DST run tional S	? 🔽	No 🗖 Ye:	s (Submit s (Submit s (Submit	report)
	T			rings set in wel		Stage C	ementer	No c	of Sks. &	1 (	Slurry Vol.			
Hole Size	Size/Gra		Vt. (#/ft.)	Top (MD)	Bottom (MD)	De		Туре	of Cemen		(BBL)	Cement	Top*	Amount Pulled
12-1/4"	8-5/8" J-		4# 0 5.5# 0		315'				ASS G	-		141		1.00
7-7/8"	5-1/2" J-	-55 18	5.5# 0		6561'				RIMLITE 1/50 POZ			44'		
	<del>                                     </del>				<u> </u>	<b>—</b>		1400 00	700.02			<u> </u>		
										1				
24. Tubing Size		Set (MD)	Packer I	Depth (MD)	Size	Depth Se	et (MD)	Packer I	Depth (MD	<u> </u>	Size	Depth Se	et (MD)	Packer Depth (MD)
2-7/8"		6054'	TA @ 56									İ		
25. Produci	ng Intervals Formation			Тор	Bottom		rforation forated In			Size	l No	Holes		Perf. Status
A) Green I		.1	456		6021'	4564-60		iicivai	.3	6"	105	110103		1 CH. Otatas
B)														
C)														
D)														
27. Acid, F	racture, Treate Depth Inter		Cement Sque	eze, etc.				Amount a	nd Type o	of Mater	rial			
4564-602			Frac	: w/479113#	20/40 white sa	nd in 3815								
											****			· · · · · · · · · · · · · · · · · · ·
28. Product	ion - Interv	1 Δ												<u> </u>
Date First		Hours	Test	Oil		Water	Oil Gra		Gas		Production			
Produced	0/00/40	Tested	Production	- 1		BBL	Corr. A	Ρl	Gravit	У	2-1/2" x 1 	-1/2" x 24' l	KHAC P	rump
12/13/ <b>1</b> Choke	2/23/12 Tbg. Press.	24 Csg.	24 Hr.	Oil		10 Water	Gas/Oil		Well S	tatus	<u></u>			
Size		Press.	Rate	BBL		BBL	Ratio			DUCIN	IG			
28a. Produc						****	<u> </u>							
Date First Produced	Test Date	Hours Tested	Test Production	Oil on BBL		Water BBL	Oil Gra Corr. A		Gas Gravit	у	Production	Method		
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	OiI BBL	1	Water BBL	Gas/Oil Ratio		Well S	Status			R	RECEIVED
*(See instr	uctions and	spaces fo	or additional	data on page 2	2)		<u> </u>						<b>j</b> t1	IN 2 1 2012

	uction - Inte Test Date	rval C Hours	Test	Oil	Gas	Water	Oil Gravity	Gas	Production Method	
Produced	Test Bute	Tested	Production	BBL	MCF	BBL	Corr. API	Gravity	roduction Memor	
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status		
28c. Prod	uction - Inte	rval D		1		J				
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method	
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	1	
29. Dispos	sition of Gas	(Solid, u	sed for fuel, ve	ented, etc.,						
USED FOR										
30. Sumn	nary of Poro	us Zones	(Include Aqui	ifers):				31. Formation	on (Log) Markers	
	ng depth int					intervals and al ng and shut-in	l drill-stem tests, pressures and	GEOLOGI	CAL MARKERS	
										Тор
Forn	nation	Тор	Bottom		Des	criptions, Conte	ents, etc.		Name	Meas. Depth
GREEN RIV	/ER	4564'	6021'					GARDEN GU GARDEN GU	LCH MARKER LCH 1	3976' 4200'
								GARDEN GU POINT 3 MRK		4320' 4592'
		:						X MRKER Y MRKR		4854' 4887'
							•	DOUGLAS CI BI-CARBONA		5009' 5266'
								B LIMESTON CASTLE PEA	K	5391' 5940'
								BASAL CARB WASATCH	ONATE	6388' 6518'
		i								
32. Additi	ional remark	s (include	plugging pro	cedure):	4					
									vunțil 2/10/2012, when it was took place on 2/11/2012.	shut in to place
22 Indian	to which its	ma hava h	oon ottochod h	v placina	a charle in the	annronriata ha	was:		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
						appropriate bo				
			(1 full set req' and cement ve			Geologic Report		Report  r: Drilling Daily A	Directional Survey Activity	
34. I herel	y certify that	at the fore	going and atta	ched info	rmation is con	nplete and corre	ect as determined f	rom all available re	ecords (see attached instructions)*	
		pring Je	nnifer Peatr	oss			Title Product Date 02/27/20	tion Technician		
	gnature	10	VVIIV				Date OFFILE	· · -		
						it a crime for a atter within its		ly and willfully to	make to any department or agency	of the United States any

(Continued on page 3) (Form 3160-4, page 2)



# **NEWFIELD EXPLORATION**

USGS Myton SW (UT) SECTION 3 T9S, R16E U-33-8-16

Wellbore #1

Design: Actual

# **Standard Survey Report**

13 April, 2012





Survey Report



Company:

NEWFIELD EXPLORATION

Project:

USGS Myton SW (UT)

Site:

SECTION 3 T9S, R16E

Well: Wellbore: U-33-8-16 Wellbore #1

Design:

Actual

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

**Survey Calculation Method:** 

Database:

Well U-33-8-16

U-33-8-16 @ 5670.0ft (NDSI SS #1)

U-33-8-16 @ 5670.0ft (NDSI SS #1)

Minimum Curvature

EDM 2003.21 Single User Db

Project

USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA

Map System:

US State Plane 1983

Geo Datum:

North American Datum 1983

Map Zone:

Utah Central Zone

System Datum:

Mean Sea Level

Site

SECTION 3 T9S, R16E

Site Position:

Northing:

7,193,000.00 ft

Latitude:

40° 3' 29.861 N

From:

Well

Мар

Easting: Slot Radius: 2,030,700.00ft

Longitude: Grid Convergence:

110° 6' 20.047 W

0.89°

Position Uncertainty:

**Position Uncertainty** 

U-33-8-16, SHL LAT: 40 03 54.11 LONG: -110 06 43.90

Well Position

+E/-W

0.0 ft 0.0 ft

0.0 ft

0.0 ft

Northing: Easting:

Wellhead Elevation:

7,195,424.44 ft 2,028,807.60 ft

5,670.0 ft

Latitude:

Ground Level:

40° 3' 54.110 N Longitude: 110° 6' 43.900 W

5,660.0 ft

Wellbore

Wellbore #1

Magnetics

**Model Name** 

Sample Date

Declination (°)

Dip Angle (°)

Field Strength

(nT)

IGRF2010

12/2/2010

11.40

65.82

52,326

Design

Actual

**Audit Notes:** 

Version:

1.0

Phase:

ACTUAL

Tie On Depth:

0.0

**Vertical Section:** 

Depth From (TVD) (ft)

0.0

+N/-S (ft) 0.0

+E/-W (ft) 0.0

Direction (°) 314.45

Survey Program

4/13/2012 Date

From (ft)

To (ft)

Survey (Wellbore)

**Tool Name** 

Description

377.0

6,576.0 Survey #1 (Wellbore #1)

MWD

MWD - Standard

Survey

Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Section	Rate	Rate	Rate
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
377.0	0.40	135.90	377.0	-0.9	0.9	-1.3	0.11	0.11	0.00
408.0	0.40	104.90	408.0	-1.1	1.1	-1.5	0.69	0.00	-100.00
439.0	0.35	48.60	439.0	-1.0	1.3	-1.6	1.15	-0.16	-181.61
469.0	0.75	18.80	469.0	-0.8	1.4	-1.5	1.60	1.33	-99.33
500.0	0.79	5.20	500.0	-0,4	1.5	-1.3	0.60	0.13	-43.87
530.0	1.00	349.90	530.0	0.1	1.5	-1.0	1.05	0.70	-51.00
561.0	1.10	336.40	561.0	0.6	1.3	-0.5	0.86	0.32	-43.55
591.0	1.80	341.00	591.0	1.3	1.0	0.2	2.36	2.33	15.33
622.0	2.40	340.00	622.0	2.4	0.6	1.2	1.94	1.94	-3.23
653.0	2.50	337.00	652.9	3.7	0.2	2.4	0.52	0.32	-9.68
683.0	2.80	322.70	682.9	4.8	-0.5	3.8	2.41	1.00	-47.67
714.0	2.90	310.80	713.9	6.0	-1.6	5.3	1.93	0.32	-38.39



Survey Report



Company:

NEWFIELD EXPLORATION

Project:

USGS Myton SW (UT)

Site: Well: SECTION 3 T9S, R16E U-33-8-16

Wellbore: Design:

Actual

Wellbore #1

Local Co-ordinate Reference:

TVD Reference:

Well U-33-8-16

U-33-8-16 @ 5670.0ft (NDSI SS #1) U-33-8-16 @ 5670.0ft (NDSI SS #1)

MD Reference:

North Reference: Survey Calculation Method:

Database:

Minimum Curvature

EDM 2003.21 Single User Db

urvey	n sa mar Nggan nggalawa Ethan	Space (political) (pa	na kadalah	wiji.			Selfino de		na utilitari ek
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°7100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
744.0	3.40	306.90	743.8	7.0	-2.9	6.9	1.81	1.67	-13.00
775.0	3.70	305.00	774.7	8.1	-2. <del>9</del> -4.4	8.8	1.04	0.97	-6.13
805.0	3.70	303.50	804.7	9.2	-6.0	10.7	0.32	0.00	-5.00
835.0	4.10	306.20	834.6	10.4	-7.7	12.8	1.47	1.33	9.00
879.0 923.0	5.00 5.60	310.40	878.5	12.5	-10.4	16.2	2.18	2.05	9.55
967.0	6.30	312.60 314.00	922.3 966.1	15.2 18.4	-13.5 -16.8	20.3 24.8	1.44 1.62	1.36 1.59	5.00 3.18
				10.4			1.02	1.59	5.10
1,011.0	7.00	312.60	1,009.8	21.9	-20.5	29.9	1.63	1.59	-3.18
1,055.0	7.70	313.30	1,053.4	25.7	-24.6	35.6	1.60	1.59	1.59
1,099.0	8.30	314.50	1,097.0	29.9	-29.0	41.7	1.42	1.36	2.73
1,143.0	8.70	313.90	1,140.5	34.5	-33.7	48.2	0.93	0.91	-1.36
1,187.0	9.30	315.90	1,183.9	39.3	-38.6	55.1	1.54	1.36	4.55
1,231.0	9.80	316.40	1,227.3	44.6	-43.6	62.4	1.15	1.14	1.14
1,275.0	10.30	317.30	1,270.7	50.2	-48.9	70.0	1.19	1.14	2.05
1,319.0	10.70	315.90	1,313.9	56.0	-54.4	78.1	1.08	0.91	-3.18
1,363.0	11.10	316.20	1,357.1	62.0	-60.2	86.4	0.92	0.91	0.68
1,407.0	11.30	316.20	1,400.3	68.2	-66.1	94.9	0.45	0.45	0.00
1,451.0	12.00	316.90	1,443.4	74.6	-72.2	103.8	1.62	1.59	1.59
1,495.0	12.90	316.50	1,486.3	81.5	-78.7	113.3	2.05	2.05	-0.91
1,539.0	13.50	317.00	1,529.2	88.9	-85.6	123.3	1.39	1,36	1.14
1,583.0	14.30	317.90	1,571.9	96.6	-92.7	133.9	1.88	1.82	2.05
1,627.0	15.00	316.40	1,614.5	104.8	-100.3	145.0	1.81	1.59	-3.41
1,671.0	15.50	314.30	1,656.9	113.0	-108.4	156.6	1.69	1.14 0.23	-4.77 -5.23
1,715.0 1,759.0	15.60 15.70	312.00 310.30	1,699.3	121.1 128.9	-117.0 -126.0	168.3 180.2	1.42 1.07	0.23	-3.23 -3.86
1,803.0	15.60	309.00	1,741.7 1,784.0	126.9	-126.0 -135.1	192.0	0.83	-0.23	-3.06 -2.95
1,847.0	15.10	307.50	1,826.5	143.7	-144.2	203.6	1.45	-1.14	-3.41
1,891.0	14.80	306.80	1,869.0	150.5	-153.3	214.9	0.80	-0.68	-1.59
1,935.0	14.20	307.50	1,911.6	157.2	-162.1	225.8	1.42	-1.36	1.59
1,979.0	14.20	307.60	1,954.2	163.8	~170.6	236.5	0.06	0.00	0.23
2,023.0	13.80	305.90	1,996.9	170.1	-179.2	247.0	1.30	-0.91	-3.86
2,067.0	12.90	300.20	2,039.7	175.7	-187.7	257.0	3.62	-2.05	-12.95
2,111.0	12.80	301.00	2,082.6	180.7	-196.1	266.5	0.46	-0.23	1.82
2,155.0	12.50	301.10	2,125.6	185.6	-204.3	275.9	0.68	-0.68	0.23
2,199.0	12.70	304.60	2,168.5	190.8	-212.4	285.3	1.79	0.45	7.95
2,243.0	12.90	310.40	2,211.4	196.8	-220.1	294.9	2.95	0.45	13.18
2,287.0	12.60	315.10	2,254.3	203.4	-227.2	304.6	2.45	-0.68	10.68
2,331.0	12.80	313.70	2,297.3	210.1	-234.2	314.3	0.83	0.45	-3.18
2,375.0	13.20	313.20	2,340.1	216.9	-241.3	324.2	0.94	0.91	-1.14
2,419.0	13.50	314.40	2,382.9	224.0	-248.7	334.4	0.93	0.68	2.73
2,463.0	14.40	316.00	2,425.6	231.5	-256.1	345.0	2.23	2.05	3.64
2,507.0	15.00	317.20	2,468.2	239.6	-263.8	356.1	1.53	1.36	2.73
2,551.0	15.60	317.70	2,510.6	248.2	-271.7	367.7	1.40	1.36	1.14
2,595.0	16.10	317.70	2,553.0	246.2 256.9	-271.7	379.7	1.43	1.14	-3.18
2,639.0	17.00	315.90	2,595.2	266.0	-288.6	392.2	2.06	2,05	-0.91
2,683.0	17.40	315.40	2,637.2	275.3	-297.6	405.3	0.97	0.91	-1.14
2,727.0	17.60	315.10	2,679.1	284.7	-307.0	418.5	0.50	0.45	-0.68
2,771.0	16.70	314.50	2,721.2	293.8	-316.2	431.5	2.08	-2.05	-1.36 7.50
2,815.0	15.40 15.60	311.20	2,763.5	302.1	-325.1	443.6 455.3	3.61	-2.95 0.23	-7.50 3.18
2,859.0 2,903.0	15.50 14.90	312.60 314.80	2,805.9 2,848.3	309.9 317.9	-333.8 -342.1	455.3 466.9	0.88 1.89	-1.36	5.00
2,903.0 2,947.0	15.30	314.00	2,646.3 2,890.8	317.9	-342.1	478.3	1.00	0.91	-1.59
2,991.0	16.10	316.80	2,933.2	334.4	-358.7	490.2	2.46	1.82	6.14
3,035.0	17.30	317.00	2,975.3	343.6	-367.3	502.9	2.73	2.73	0.45



Survey Report



Company:

**NEWFIELD EXPLORATION** 

Project:

USGS Myton SW (UT)

Site: Well: SECTION 3 T9S, R16E U-33-8-16

Wellbore: Design:

Wellbore #1 Actual

Local Co-ordinate Reference:

TVD Reference:

U-33-8-16 @ 5670.0ft (NDSI SS #1)

MD Reference: North Reference: U-33-8-16 @ 5670.0ft (NDSI SS #1)

Well U-33-8-16

Survey Calculation Method: Database:

Minimum Curvature

EDM 2003.21 Single User Db

ey							Mada Maria		
Measured Depth (ft)	Inclination (°)	Azimuth	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
3,079.0	18.60	317.00	3,017.2	353.6	-376.6	516.4	2.95	2.95	0.00
3,123.0	19.40	316.50	3,058.8	364.0	-386.4	530.7		1.82	-1.14
			•				1.86		
3,167.0	18.60	316.40	3,100.4	374.4	-396.2	545.0	1.82	-1.82	-0.23
3,211.0	18.20	315.90	3,142.1	384.4	-405.9	558.9	0.98	-0.91	-1.14
3,255.0	18.90	316.70	3,183.9	394.5	-415.5	572.9	1.69	1.59	1.82
3,298.0	19.70	316.10	3,224.4	404.8	-425.3	587.1	1.92	1.86	-1.40
3,343.0	18.80	313.30	3,266.9	415.2	-435.9	601.9	2.86	-2.00	-6.22
3,387.0	18.10	311.60	3,308.7	424.6	-446.1	615.9	2.01	-1.59	-3.86
3,431.0	18.70	311.60	3,350.4	433.9	-456.5	629.7	1.36	1.36	0.00
3,475.0	19.50	312.44	3,392.0	443.5	-467.2	644.1	1.92	1.82	1.91
3,519.0	19.70	313.10	3,433.4	453.5	-478.1	658.9	0.68	0.45	1.50
3,563.0	19.80	313.70	3,474.9	463.7	-488.9	673.7	0.51	0.23	1.36
3,607.0	19.60	314.00	3,516.3	474.0	-499.6	688.6	0.51	-0.45	0.68
3,651.0	19.80	315.00	3,557.7	484.4	-510.1	703.4	0.89	0.45	2.27
3,696.0	19.50	314.40	3,600.1	495.1	-510.1 -520.9	703.4 718.5	0.80	-0.67	-1.33
3,740.0	18.90	313.00	3,641.6	495.1 505.1	-520.9 -531.3	718.5 733.0		-0.67 -1.36	-1.33 -3.18
							1.72		
3,784.0 3,828.0	18.90 18.20	313.70 313.30	3,683.3 3,725.0	514.8 524.5	-541.7 -551.9	747.2 761.2	0.52 1.62	0.00 -1.59	1.59 -0.91
3,872.0	17.35	311.00	3,766.9	533.5	-561.8	774.7	2.51	-1.93	-5.23
3,916.0	17.00	311.00	3,808.9	542.0	-571.6	787.6	0.80	-0.80	0.00
3,960.0	15.95	310.70	3,851.1	550.2	-581.1	800.1	2.39	-2.39	-0.68
4,004.0	15.40	312.00	3,893.5	558.0	-590.0	811.9	1.48	-1.25	2.95
4,048.0	14.90	312.10	3,935.9	565.7	-598,5	823.4	1.14	-1.14	0.23
4,092.0	14.70	313.10	3,978.5	573.3	-606.8	834.7	0.74	-0.45	2.27
4,136.0	14.90	315.00	4,021.0	581.2	-614.9	845.9	1.19	0.45	4.32
4,181.0	14.90	317.00	4,064.5	589.5	-622.9	857.5	1.14	0.00	4.44
4,225.0	15.20	318.00	4,107.0	597.9	-630.6	868.9	0.90	0.68	2.27
4,269.0	15.20	318.20	4,149.5	606.5	-638.3	880.4	0.12	0.00	0.45
4,313.0	14.90	317.00	4,191.9	614.9	-646.0	891.8	0.98	-0.68	-2.73
4,357.0	14.90	317.00	4,234.5	623.2	-653.7	903.1	0.00	0.00	0.00
4,401.0	14.40	318.00	4,277.0	631.4	-661.3	914.2	1.27	-1.14	2.27
4,445.0	13.70			639.4	-668.4			-1.14 -1.59	
4,488.0	13.40	318.40 318.00	4,319.7 4,361.5	646.9	-675.1	924.9 934.9	1.61 0.73	-0.70	0.91 -0.93
4,532.0	13.40	317.80	4,404.3	654.4	-681.9	945.1	0.11	0.00	-0.45
4,577.0	13.20	315.70	4,448.1			955.4	1.16	-0.44	-4.67
4,620.0	13.10	315.40	4,490.0	669.0	-695.9	965.2	0.28	-0.23	-0.70
4,665.0	12.80	314.20	4,533.8	676.1	-703.0	975.3	0.90	-0.67	-2.67
4,709.0	13.10	313.30	4,576.7	682.9	-710.2	985.2	0.82	0.68	-2.05
4,753.0	13.40	314.20	4,619.6	689.9	-717.4	995.3	0.83	0.68	2.05
4,796.0	13.50	315.40	4,661.4	696.9	-724.5	1,005.3	0.69	0.23	2.79
4,840.0	13.10	316.40	4,704.2	704.2	<i>-</i> 731.6	1,015.4	1.05	-0.91	2.27
4,883.0	13.20	317.70	4,746.1	711.3	-738.2	1,025.1	0.73	0.23	3.02
4,927.0	13.40	316.60	4,788.9	718.8	-745.1	1,035.3	0.73	0.45	-2,50
4,971.0	13.80	316.90	4,831.7	726.3	-752.2	1,045.6	0.92	0.91	0.68
5,015.0	14.50	316.80	4,874.3	726.3	-752.2 -759.6	1,045.6	1.59	1.59	-0.23
5,059.0	15.10	316.40	4,916.9	742.3	-767.3	1,056.5	1.38	1.36	-0.91
5,103.0	15.10	317.70	4,959.3	742.3 750.9	-707.3 -775.3	1,007.0		1.59	2.95
5,144.2	15.43	316.58	4,959.5 4,998.9	750.9 759.0	-775.3 -782.8	1,079.3	1.77 1.17	-0.91	-2.72
		30.01	4,996.9	759.0	-/ 0∠.8	1,090.4	1.17	-0.91	-2.12
U-33-8-16 TG									
5,147.0	15.40	316.50	5,001.7	759.6	-783.3	1,091.1	1.17	-0.90	-2.79
5,191.0	15.30	314.40	5,044.1	767.9	-791.5	1,102.7	1.28	-0.23	-4.77
5,235.0	15.80	313.70	5,086.5	776.1	-800.0	1,114.5	1.21	1.14	-1.59
5,279.0	16.10	315.00	5,128.8	784.5	-808.6	1,126.6	1.06	0.68	2.95
5,323.0	16.20	315.00	5,171.0	793.2	-817.3	1,138.9	0.23	0.23	0.00



Survey Report



Company:

NEWFIELD EXPLORATION

Project:

USGS Myton SW (UT)

Site: Well: SECTION 3 T9S, R16E

Wellbore:

U-33-8-16 Wellbore #1

Design:

Actual

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

Survey Calculation Method: Database:

Well U-33-8-16

U-33-8-16 @ 5670.0ft (NDSI SS #1)

U-33-8-16 @ 5670.0ft (NDSI SS #1)

Minimum Curvature

EDM 2003.21 Single User Db

Measured							<u> </u>	• •	
Measured Depth	Inclination	a	Vertical Depth		. =	Vertical Section	Dogleg Rate	Build Rate	Turn Rate
(ft)	(°)	Azimuth (°)	(ft)	+N/-S (ft)	+E/-W (ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)
5,367.0	16.30	315.10	5,213.3	801.9	-826.0	1,151.2	0.24	0.23	0.23
5,411.0	16.30	316.90	5,255.5	810.8	-834.6	1,163.5	1.15	0.00	4.09
5,455.0	16.10	315.90	5,297.8	819.6	-843.0	1,175.8	0.78	-0.45	-2.27
5,499.0	16.20	314.00	5,340.0	828.3	-851.7	1,188.0	1.22	0.23	-4.32
5,543.0	16.50	315.90	5,382.3	837.0	-860.4	1,200.4	1.39	0.68	4.32
5,587.0	17.00	317.40	5,424.4	846.3	-869.2	1,213.1	1.50	1.14	3.41
5,631.0	16.80	319.00	5,466.5	855.8	-877.7	1,225.8	1.15	-0.45	3.64
5,675.0	17.30	320,00	5,508.6	865.6	-886.1	1,238.7	1.32	1.14	2.27
5,719.0	17.70	319.40	5,550.5	875.7	-894.6	1,251.9	1.00	0.91	-1.36
5,763.0	18.50	321.40	5,592.3	886.2	-903.3	1,265.5	2.30	1.82	4.55
5,807.0	19.30	322.00	5,634.0	897.4	-912.2	1,279.6	1.87	1.82	1.36
5,851.0	19.40	320.00	5,675.5	908.7	-921.3	1,294.1	1.52	0.23	-4.55
5,895.0	18.25	317.40	5,717.1	919.4	-930.7	1,308.2	3.23	-2.61	-5.91
5,939.0	16.75	315.00	5,759.1	929.0	-939.8	1,321.5	3.78	-3.41	-5.45
5,983.0	16.00	314.00	5,801.3	937.7	-948.7	1,333.9	1.82	-1.70	-2.27
6,027.0	16.50	312.00	5,843.5	946.1	-957.7	1,346.2	1.71	1.14	-4.55
6,071.0	16.60	311.70	5,885.7	954.4	-967.0	1,358.7	0.30	0.23	-0.68
6,115.0	15,60	311.40	5,928.0	962.5	-976.2	1,370.9	2.28	-2.27	-0.68
6,159.0	14.70	313.60	5,970.5	970.3	-984.6	1,382.4	2.43	-2.05	5.00
6,203.0	14.30	317.00	6,013.1	978.1	-992.4	1,393.4	2.14	-0.91	7.73
6,247.0	14.10	319.50	6,055.7	986.2	-999.6	1,404.1	1.47	-0.45	5.68
6,291.0	13.50	320.60	6,098.5	994.2	-1,006.3	1,414.6	1.49	-1.36	2.50
6,335.0	13.18	317.80	6,141.3	1,001.9	-1,012.9	1,424.7	1.64	-0.73	-6.36
6,379.0	12.70	315.50	6,184.2	1,009.0	-1,019.7	1,434.5	1.60	-1.09	-5.23
6,423.0	12.13	314.00	6,227.1	1,015.7	-1,026.4	1,444.0	1. <del>4</del> 9	-1.30	-3.41
6,467.0	11.40	314.30	6,270.2	1,022.0	-1,032.9	1,453.0	1.66	-1.66	0.68
6,511.0	10.72	314.60	6,313.4	1,027.9	-1,038.9	1,461.4	1.55	-1.55	0.68
6,524.0	10.40	314.40	6,326.2	1,029.5	-1,040.6	1,463.8	2.48	-2.46	-1.54

Checked By:	Approved By:	Date:	




Project: USGS Myton SW (UT) Site: SECTION 3 T9S, R16E Well: U-33-8-16 Wellbore: Wellbore #1


Design: Actual



Azimuths to True North Magnetic North: 11.40°

Magnetic Field Strength: 52325.8snT Dip Angle: 65.82° Date: 12/2/2010 Model: IGRF2010





Design: Actual (U-33-8-16/Wellbore #1)

Created By: Sarah Well

Date:

11:47, April 13 2012

THIS SURVEY IS CORRECT TO THE BEST OF MY KNOWLEDGE AND IS SUPPORTED BY ACTUAL FIELD DATA

# **Daily Activity Report**

# Format For Sundry GMBU U-33-8-16 8/1/2011 To 12/30/2011

GMBU U-33-8-16

**Waiting on Cement** 

**Date:** 10/4/2011

Ross #26 at 314. Days Since Spud - 313.92'KB. On 10/4/11 cement w/BJ w/160 sks of class G+2%kcl+.25#CF mixed @ 15.8ppg and 1.17 - On 9/29/11 Ross #26 spud and drilled 315' of 12 1/4" hole, P/U and run 7 jts of 8 5/8" casing set - yield. Returned 9bbls to pit, bump plug to 500psi, BLM and State were notified of spud via email.

Daily Cost: \$0

Cumulative Cost: \$54,293

#### GMBU U-33-8-16

#### Drill 7 7/8" hole with fresh water

**Date:** 10/24/2011

NDSI SS #1 at 3440. 1 Days Since Spud - Rig Service, check crownomatic and BOP - Drill 7 7/8" hole F/ 582 to 3440' w/ 20K WOB,TRPM-175,GPM-390,Avg ROP-211 ft/hr - No H2S or flow in last 24 hours - Drill 7 7/8" hole F/ 308' to 582' w/ 18K WOB,TRPM-175,GPM-390,Avg ROP-137 ft/hr - R/U B&C Quicktest & test top drive,pipe&blind rams,choke to 2000#/10min,casing to 1500#/30min - Move rig , set equipment, and rig up - Pick up BHA and directional tools and scribe, tag @ 308'

Daily Cost: \$0

**Cumulative Cost:** \$92,426

#### **GMBU U-33-8-16**

# Drill 7 7/8" hole with fresh water

Date: 10/25/2011

NDSI SS #1 at 5596. 2 Days Since Spud - No H2S or flow in last 24 hours - Drill 7 7/8" hole F/ 3440' to 4716' w/ 20K WOB,TRPM-175,GPM-390,Avg ROP-122 ft/hr - Rig Service, check crownomatic and BOP, H2S Alarm went off, suited up and verify = 0 H2S, sensor bad - Drill 7 7/8" hole F/ 4716' to 5596' w/ 20K WOB,TRPM-175,GPM-390,Avg ROP-68 ft/hr

Daily Cost: \$0

Cumulative Cost: \$130,050

#### **GMBU U-33-8-16**

Rig up to run casing

**Date:** 10/26/2011

NDSI SS #1 at 6576. 3 Days Since Spud - Circulate and condition hole For lay down Check flow=No flow - Drill 7 7/8" hole F/ 5596' to 6576' w/ 20K WOB,TRPM-175,GPM-390,Avg ROP-93 ft/hr - R/U PSI & log, loggers TD=6566' to surface,(dual guard,gamma ray,density) tool failure - R/U B&C Quicktest and test casing rams to 2000#/10 min - Rig up to run casing and start run - Lay down drill pipe and BHA

Daily Cost: \$0

Cumulative Cost: \$189,327

#### GMBU U-33-8-16

Rigging down

**Date:** 10/27/2011

NDSI SS #1 at 6576. 4 Days Since Spud - of tail (50:50:2+.05#SF+3%KCL+.5%EC-1+.25#CF) @ 14.4ppg and 1.24 yield, displaced w/ 155 bbls of - Cement w/ 235 sks of lead (PLII+.05ESF+3%KCL+.5#CF+2#kol seal) @ 11ppg and 3.53 yield, and 460 sks - Run 155 jts of 5.5#LTC set @ 6560.53' w/ landing mandril,short jt @ 3740.87' - Release rig @ 1930 on 10-26-11. - Clean mud tanks - fresh, bump plug to 1850psi, returned 10 bbls

cement to pit, BLM and State were notified via email - Circulate casing and rig up Baker

Hughes Finalized

Daily Cost: \$0 Cumulative Cost: \$308,729

**Pertinent Files: Go to File List** 

Sundry Number: 77021 API Well Number: 43013506940000 FEDERAL APPROVAL OF THIS ACTION IS NECESSARY

	FORM 9				
ı	5.LEASE DESIGNATION AND SERIAL NUMBER: UTU-77338				
SUNDR	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:				
Do not use this form for pro current bottom-hole depth, I FOR PERMIT TO DRILL form	7.UNIT or CA AGREEMENT NAME: GMBU (GRRV)				
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: GMBU U-33-8-16				
2. NAME OF OPERATOR: NEWFIELD PRODUCTION CO	<b>9. API NUMBER:</b> 43013506940000				
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT,		ONE NUMBER: t	9. FIELD and POOL or WILDCAT: MONUMENT BUTTE		
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0782 FNL 0769 FWL			COUNTY: DUCHESNE		
QTR/QTR, SECTION, TOWNSH Qtr/Qtr: NWNW Section:	HP, RANGE, MERIDIAN: 03 Township: 09.0S Range: 16.0E Meridian	: S	STATE: UTAH		
11. CHECI	K APPROPRIATE BOXES TO INDICATE N	ATURE OF NOTICE, REPOR	T, OR OTHER DATA		
TYPE OF SUBMISSION		TYPE OF ACTION			
This well has had a bit and scraper in o	CHANGE TO PREVIOUS PLANS  CHANGE WELL STATUS  DEEPEN  OPERATOR CHANGE  PRODUCTION START OR RESUME  REPERFORATE CURRENT FORMATION  TUBING REPAIR  WATER SHUTOFF	eld will be running a with the intention to well back up to	CASING REPAIR  CHANGE WELL NAME  CONVERT WELL TYPE  NEW CONSTRUCTION  PLUG BACK  RECOMPLETE DIFFERENT FORMATION  TEMPORARY ABANDON  WATER DISPOSAL  APD EXTENSION  OTHER: Well Clean Out  Pepths, volumes, etc.  Accepted by the Utah Division of Oil, Gas and Mining  Date: January 05, 2017  By:		
NAME (PLEASE PRINT)	PHONE NUMBER	TITLE			
Mandie Crozier SIGNATURE	435 646-4825	Regulatory Tech  DATE			
N/A		12/20/2016			